

AML PROJECT 160 – McINTOSH PIT EVAPORATIVE DEWATERING & BACKFILL



ASRS Laramie 2026



Bottom Line Takeaways

Backfill Management


- Backfill material will segregate upon introduction to water body
 - Fill Stability Considerations
 - Slimes Accumulation
- Fill introduction rate is ideally performed to roughly match effective evaporation rate/volume
 - Phased work essential
- Phased interim grading surfaces must
 - Maintain fill stability
 - Manage internal drainage
 - Allow for Deployment and maintenance of Evaporative systems, allow for winterizing in off season

Evaporative Dewatering

- System evaporation rate $\geq$ Effective evaporation rate
 - Mine open pits are not closed systems
 - System operating parameters are rarely ideal
- \$ Discharge Dewatering < \$ Evaporative Dewatering (lined electrical power) < \$ Evap. Dewatering (*Deisel Genset*)
- Evaporative dewatering is not effective in all seasons and all climates
 - Phase work essential
- Land vs. Water Deployed evap. arrays have tradeoffs (evaporation rate, erosion, access, footprint, maintenance etc.)

McIntosh Location and History

- Project is located approximately 10 miles south of Jeffrey City, Wyoming
- Ore grade uranium discovered in Crooks Gap District in 1953
- Commercial production began 1957
- Production at McIntosh ceased 1982
- Ownership passed to current owner Energy Fuels in 2012




McIntosh Pit Overview

- 30.3 acre water body
- Excavation Magnitude
 - ~20 million CY mine pit excavation
 - ~11.7 million CY reclamation backfill volume placed in pit
- ~1 billion gallons water in pit
- Up to 240 feet deep water body
- Up to 200 foot highwalls above water line




West Highwall and Pit Water Prior to Reclamation


Backfill Sequence Photos



Pit Water Elevation Timeline



Pre-Reclamation Condition E-W View




Backfill Phase 1



Dozers Pushing Blasted Material From Highwall into the Pit


Backfill Phase 1

- Phase 1 blasted and dozed rocky spoils into water filled pit
- Fines settled into a layer in the bottom of the pit
- Minimal change in surface area of pit water body at end of phase
- Max depth of water ~252 ft



Backfill Phase 2

- Phase 2 continued to blast and doze rocky spoils into water filled pit
- Fines again settled into a layer in the bottom of the pit
- Minimal change in surface area of pit water body at end of phase
- Max water depth reduced to ~95 ft




Backfill Phase 2



Dozers Reducing West Highwall


Backfill Phase 2C

- Phase 2C dozed spoils into water filled pit on top of rock foundation from prior phases
- Water began to be crowded north as surface area of water body shrank
- Max water depth remained ~95 ft




Backfill Phase 3

- Phase 3 dozed additional spoils into water filled pit on top of rock foundation from prior phases
- Water continued to be crowded north as surface area of water body shrank
- Max depth reduced to ~68 ft



Backfill Phase 4

- Phase 4 dozed additional spoils into water filled pit
- Water continued to be crowded north as surface area of water body decreased
- Max depth reduced to ~53 ft




Backfill Summary

Phase	Pit Water Elevation (Feet)	Maximum Depth of Water (Feet)	Deepest Pit Elevation (Feet)	Depth to Average Pit Bottom (Feet)	Average Pit Bottom Elevation (Feet)
Pre-Project	6,783	244	6,539	173	6,610
Post Phase 1	6,801.5	251.5	6,550	171.5	6,630
Post Phase 2	6,813.8	94.8	6,719	92.8	6,721
Post Phase 2C	6,815.4	95.4	6,720	85.4	6,730
Interim Phase 3	6,816.4	75.4	6,741	70.4	6,746
Post Phase 3	6,812.1	68.1	6,744	61.1	6,751
Post Phase 4	6817.7	52.7	6,765	38.7	6,779
Post Phase 5	COMPLETE				

Dewatering Parameters Overview

- Initial Maximum Water depth >240'
- ~1 billion gallons water
- Offsite discharge not permissible by Wyoming DEQ



- Evaporative Dewatering Needed
- Initial Evaporation rate designed to approximate equal displacement due to backfill



West Highwall and Pit Water Prior to Reclamation


Initial System Design

- Evaporative dewatering system proposed to remove 800 gpm, 24h/d, 7d/wk during six highest evaporation months (April-September)
 - Evaporative array floated on pit water surface due to lack of access
 - Vendor estimated 10-25% evaporation rate
 - Highest net effective evaporation rate for water and land arrays was 7.3%



Disel Pump and Tank Powering Floating Arrays

Pre-Reclamation Condition N-S View



Phase 1

- Rental equipment
- Two Godwin Dri-Prime HL225M Diesel Pumps
- Two floating arrays
 - 6-inch HDPE
 - 76 feet x 276 feet
 - 75 nozzles / array
 - 4-foot risers
 - 55 psi at nozzle
- Began operation August 2014
- Operated to November
- Winterized by removing from water



Two Floating Arrays Operating in 2014

Lessons Learned and Improvements

- Rapid increase in water elevation during Phase 1 winter backfill
 - August 2014: 6,778 feet
 - April 2015: 6,802 feet
- Significant downtime for diesel pump fueling, maintenance, mechanical issues
- Electric pumps estimated to save >\$1 million compared to diesel
- Powerlines and two 200 HP Godwin Dri-Prime WT225M electric pumps installed for Phase 2
- Added floating array for Phase 2
 - Same design with 6-foot risers



Electric Power for Dewatering Arrays

Phase 2

- Damage was sustained to pumps and arrays from highwall blasting in May 2015 (Shot 1)
 - Repaired by June 5
- June 30 and July 10 (Shots 5 & 6) blasting caused more array damage
 - Repaired by September 1
- Significant downtime increased pit water level
 - April 2015: 6,802 feet
 - July 2015: 6,819 feet

Shot 1 on 5/8/2015



Shot 6 on 7/10/2015

Phase 2C

- One floating array removed
- One land-based evaporation array added
 - Two parallel 1000-foot, 12-inch HDPE lines
 - 80 nozzles at 25 feet spacing
 - One 400 HP Godwin Dri-Prime HL250M electric pump
- Water level successfully managed by upgraded system during the Phase
 - April 2016: 6,811 feet
 - December 2016: 6,815 feet
- Underwater survey showed pit bottom raised 8 feet during Phase due to backfill



Land Based Evaporation Array

Phase 3 Upgrades

- In the 2017 season backfilling operations began significantly shrinking surface area of the pit water
 - Vertical displacement became more rapid due to decreased surface area
 - Six Pole Cat turbine evaporators added
 - 75 HP high pressure HL100M booster pump



Phase 3 (2017)

- Phase began April 2017
- Evaporation unable to match displacement due to backfill
 - April 2017: 6,814 feet
 - August 2017: 6,822 feet
- AML issued Stop Work Order August 2017
 - Contractor moved equipment to nearby job
- Only evaporation performed for remainder of 2017
 - November 2017: 6,816 feet
- No further upgrades made to system



08.10.2017 17:10

Phase 3 (2018)

- Start Work Order issued August 2018
- Evaporation unable to match displacement due to backfill
 - August 2018: 6,804 feet
 - November 2018: 6,812 feet



All Dewatering Systems Operating at the Start of 2018

Phase 4

- Rising water levels necessitated raising fill around the pit
 - June 2019: 6,808 feet
 - November 2019: 6,818 feet
- August 2019 failing HL250 pump replaced with Vertical Industrial Turbine (VIT) on a floating barge
 - Higher flow of VIT pump caused flooding and erosion of Pole Cat bench
 - Water diverted away and pump rpm decreased




Rebenching to Raise the Elevation of a Pump

Floating Barge with VIT

Backfill Phase 5

- Phase 5 dozed additional spoils into water filled pit
- Water was fully entrained
- Slimes either encapsulated or handled and spread to dry



Phase 5

- Final Phase of backfill into water body
- Floating evaporative dewatering arrays operated until removal required to complete backfill
- Pit water elevation on October 15, 2020 (end of dewatering): 6,814 feet
- Turbine evaporators and land evaporators operated until impractical
- Remaining pit water pumped to McIntosh Reservoir No. 1
- No water remained by end of 2020



Mud Displaced by Fill along East Side of Pit

Mud Handling

- Mud handling was conducted in Phases 5 & 6 upon completion of dewatering
- Phase 5 removed 15,000 CY mud and spread it for drying with the remainder being encapsulated in fill
- Mud left to dry at end of Phase 5 was still saturated at the beginning of Phase 6
- Excavated spoils were mixed with mud to dry it for compaction and stabilization
- Total Mud Handling Cost \$74,882.50



Encapsulation of Remaining Mud at end of Phase 5

Backfill Phase 5



Fill From Spoils Advancing into the McIntosh Pit

Decommissioning

- Reusable equipment and materials removed from site for resale
- Non-reusable materials disassembled and properly disposed
- Decommissioning completed in 2022



Dry McIntosh Pit with Equipment Being Decommissioned

Evaporative Dewatering Summary

Phase	Start Date	End Date	Total Volume Pumped (million gallons)	Calculated Evaporation (million gallons)	Effective Evaporation Rate	Annual Costs
1	8/12/2014	11/4/2014	619.5	21.1	3.4%	\$1,171,077.85
2	8/26/2015	10/30/2015	577.7	33.6	5.8%	\$87,368.01
2C	4/21/2016	11/17/2016	1,878.0	127.5	6.8%	\$301,303.36
3 (2017)	4/19/2017	11/16/2017	1,912.5	116	6.1%	\$814,908.45
3 (2018)	4/10/2018	11/15/2018	1,848.0	108.9	5.9%	\$482,401.90
4	5/2/2019	10/25/2019	1,704.2	101.6	6.0%	\$351,273.07
5	5/1/2020	10/23/2020	1,575.5	114.7	7.3%	\$333,438.27
6	n/a	n/a	n/a	n/a	n/a	\$11,530.00
7	n/a	n/a	n/a	n/a	n/a	\$44,550.00
Total			10,115.4	623.4	6.2% AVG.	\$3,597,670.91

Evaporation Overview

- Initial pit water volume:
 - ~1 billion gallons
- Actual evaporation volume:
 - 623.4 million gal (62.3%)
- Net effective evaporation rate:
 - Initial Estimate: 10-25%
 - Actual/Effective: 6.2%
 - Pit **Not** a closed system
- Effective evaporation rate
 - Observed Water level
 - Ground water flow
 - Precipitation/runoff
- Actual evaporation > effective evaporation for 16O project



09.12.2

Evap. System Challenges


- Raising pump benches and moving land pumps in response to water elevation changes
- Net effective evaporation rate lower than theoretical max rate
- Mechanical failures
- Blasting damage risk
- Erosion mgmt
- Waterbody Safety
- Freezing winter weather
- Electrical issues



Erosion undercutting water array system

Array Comparison

- Floating array advantages:
 - Limited working space
 - Smaller pumps
 - No erosion or land saturation
- Land array advantages:
 - Ease/safety of maintenance
 - Better evaporation rate
 - 5.8% for water arrays
 - 11.2% for land arrays
 - Less wind/water damage
- Turbine evaporators – Not possible to separate performance from land and floating arrays due to limited use



Turbine Evaporator Spraying Water

Challenges and Iterations

- Volume: 10.1 billion gallons pumped total
 - 623.4 million gallons evaporated
 - 3,200 gallon/min pump rate
- Equipment:
 - Initial/Vendor estimated 2 arrays
 - Actual/Project required 4 arrays
- Time:
 - Estimated: 5 years pumping
 - Actual: 7 years pumping



Water Array Phase 4

Budget


- Original Cost Estimate:
\$3,674,000.00
- Actual Cost:
\$3,597,670.91
 - Savings: 2.1%
- General Breakdown
 - Capital costs:
\$1,957,491.68
 - Operating Costs:
\$1,640,179.23



Land and Water Arrays in Phase 2C

Evaporative Dewatering Cost Breakdown

2014-2022 Evaporative Dewatering Cost Breakdown



Evaporative Dewatering Summary




- Electric pump savings
 - No rebuilding or replacement
 - Greater reliability
 - Diesel pump cost:
~\$30,000 / month
 - Electric pump cost:
~\$6,000 / month
 - Savings: ~\$2,400,000 versus
diesel pumps
- Offsite discharge comparison
 - McIntosh evaporative
dewatering: \$5.77 / 1000 gal
 - Day Loma offsite discharge:
\$1.68 / 1000 gal



Final McIntosh Pit condition => Reservoir No. 1

- Clean surface water impoundment constructed in pit fill during Phases 4 & 5
- Backfill of pit created an artificial aquifer
- Productive water well drilled into backfill 2020 in south and 2024 into the artificial aquifer
- Water Monitoring concluded by AML in 2025





Questions?

